

Sl No		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
				Unit	Rate in Words	Rate in Figures
1		2	3	4	5	6
42		31.92	Providing and fixing dadoing with Glazed tiles of approved size, make & sample and of 6mm minimum thick of first quality, conforming to IS specifications, set in cement mortar 1:3 (1 cement : 3 fine sand) 10mm thick with a thin coat of cement slurry on the rough plastered surfaces including finishing the joints with matching coloured cement, oxalic acid wash, waxing, curing etc. with all lead and lift etc. complete as per the directions of the Engineer-in-charge including cost & conveyance of all materials, cost of labour for all items of work, equipment and all other incidental charges for the successful completion of the work.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	1215.65	Rupees One Thousand Two Hundred Fifteen And Paise Sixty Five Only
43		90.48	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains, including cost of all materials, mortar, labour, etc., Complete as per specification.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	1261.01	Rupees One Thousand Two Hundred Sixty One And Paise One Only
44		7.56	Providing and laying pattern flooring for staircase treads and risers using the combination of 20mm thick ruby red granite @ 66%, 20 mm thick grey granite @ 20%, 20mm thick, 20mm thick black granite 14%. The granite materials are laid on existing bed of CM 1:3 20mm thick pointed with colour pigment, including full rounding for nosing, flaming the ruby red granite for 50 mm wide curing etc., complete as per specification.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	6491.02	Rupees Six Thousand Four Hundred Ninety One And Paise Two Only
45		0.1	Providing Honne wood frames for doors, wrought, framed or assembled including making plaster grooves (excluding cost of concrete and side clamps) including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer. (samples to be got approved before execution). as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Cum	116637.57	Rupees One Lakh(s) Sixteen Thousand Six Hundred Thirty Seven And Paise Fifty Seven Only
46		2	Fixing of Door frames in an existing opening including embedding frame in floor and walls after cutting masonry for embedding holdfasts including providing & fixing 3/4 of MS hold fasts of size 200x20x3mm for each side and fixed to the frame and embeded with PCC 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size), painting two coats of coal tar to sides of frames, making good the damages to walls & floor as required and disposal of debris including cost of materials, labour, HOM of machineries complete as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	1195.24	Rupees One Thousand One Hundred Ninety Five And Paise Twenty Four Only
47		4.62	Providing and fixing in position shutters for doors made out of Honne wood styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 18mm thick of exterior grade plain particle board including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34, 9.26.3 as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	3876.01	Rupees Three Thousand Eight Hundred Seventy Six And Paise One Only

Contractor

SI No		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
				Unit	Rate in Words	Rate in Figures
1	2	3		4	5	6
48	9.68		Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg/m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1 mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS. using aluminium section anodized to 12 -	Sqm	3667.36	Rupees Three Thousand Six Hundred Sixty Seven And Paise Thirty Six Only
49	245.7		Providing and fixing MS grill work for windows and ventilators weighing 21 Kg./sqm. using MS flats or MS square bars or combination of MS flats and square bars as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat red lead primer & two coats synthetic enamel paint, cost of materials, fixtures, labour and HOM of machinery complete as per technical specification and as directed by the Engineer-in-Charge of work.with all lead & lift, loading & unloading and all other incidental charges etc. as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Kg	88.45	Rupees Eighty Eight And Paise Forty Five Only
50	10530		Fabricating, supplying & erecting M.S. angular Truss of span upto 10m. The bottom & top member is provided with 50x50x6mm double equal angles, welded back to back and in between top & bottom line, in areas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided. All the members are welded together with 6mm gusset plate as per Drawing No.CBS/ SD/K-Mantap/9/MND/97. The entire truss is anchored in RCC column by using 4 Nos. of M.S. anchor bolts at each support, with 10mm thick base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and welding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc., complete as per specification.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Kg	132.68	Rupees One Hundred Thirty Two And Paise Sixty Eight Only
51	175.5		Providing and fixing 6mm Bronze Multi wall poly carbonate sheet for Tubular structure. The work including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipment, complete as per specification.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	2823.66	Rupees Two Thousand Eight Hundred Twenty Three And Paise Sixty Six Only
52	18		Providing and fixing 1 mm thick M.S. sheet sliding shutters with frame and diagonal braces of 40x40x6 mm angle Iron 3.15mm thick M.S. Gusset plates at junctions and corners, 25mm dia pulley, 40x40x6 mm angles and T iron guide rail top and bottom respectively with handles, stoppers and locking arrangements etc., including applying a priming coat of red lead paint cost of materials, labour, HOM of machinery complete as per specifications. 1 double leaf door of size 2.4x2.4m Specification No. KBS 7.8 I 7.12 as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	3209.22	Rupees Three Thousand Two Hundred Nine And Paise Twenty Two Only

Contractor

S/		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
No	Unit			Rate in Words	Rate in Figures	
1	2	3		4	5	6
53	✓ 19.8	Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single groove and double groove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single groove section 2.541 kg/m. and double groove section 2.683 kg/m and bottom bottom member 114.3 mm x 44.45 mm 3.18 mm thick and 2.6 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick pre laminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and ived to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak woodgutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beamsat top and floor at bottom, including cutting chistling and making goodwith cement mortar to match the surface, providing and fixing bottompanel filled with the	✓ Sqm	✓ 5364.95	Rupees Five Thousand Three Hundred Sixty Four And Paise Ninety Five Only	
54	✓ 1	Over Head Synthetic Tanks - Providing, Placing on Terrace, Polyethylene storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet,outlet and over two pipes including cost of all materials, labour, transport charges, HOM of eipments and testing complete as per specifications for 2000 Litres Capacity including cost of all materials, formwork, labour charges, HOM of Machineries, loading, unloading ,with all lead and lifts etc., compelte & as per specification and as directed by Engineer. ---- All terms and conditions are as per Tender Document	✓ Nos	✓ 9601.58	Rupees Nine Thousand Six Hundred One And Paise Fifty Eight Only	
55	✓ 27	Providing and fixing Chorinated Poly Vynyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 M spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (Concealed work including cutting chases and good the walls etc.) 25mm nominal OD pipesas per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	✓ M	✓ 283.50	Rupees Two Hundred Eighty Three And Paise Fifty Only	
56	✓ 2	Providing and fixing white vitreous china clay, flat back wash basin size 450x300mm with a single 15mm C.P brass pillar tap with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. ---- All terms and conditions are as per Tender Document	✓ Nos	✓ 2981.29	Rupees Two Thousand Nine Hundred Eighty One And Paise Twenty Nine Only	
57	✓ 8	Providing and fixing in position brass bib cock of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	✓ Nos	✓ 308.45	Rupees Three Hundred Eight And Paise Forty Five Only	
58	✓ 4	Sluice/ gate Valves: Providing and Fixing of Gun Metal wheel Sluice Valve for the Distribution Mains of Water Supply Scheme, Conforming to Isand of approved make as the directions including cost of material, labour, lead complete for 25 mm dia pipe lines as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	✓ Nos	✓ 572.67	Rupees Five Hundred Seventy Two And Paise Sixty Seven Only	
59	✓ 2	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C. I M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	✓ Nos	✓ 5817.42	Rupees Five Thousand Eight Hundred Seventeen And Paise Forty Two Only	

Contractor

SI		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
				Unit	Rate in Words	Rate in Figures
1	2	3		4	5	6
60	2	✓	Providing white vitreous china clay Indian pattern squatting urinals with white glazed foot rests of approved quality and make conforming to ISI specifications and fixing in Position with M-15 as directed of size 50.8 cms X 38 cms X 10.16 cms -A Grade (Rate includes cost of all materials and conveyance to work spot).as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	1099.98	Rupees One Thousand Ninety Nine And Paise Ninety Eight Only
61	2	✓	Providing and fixing 600x450mm bevellead edge mirror of superior glass with 6mm hard board backing and fixed to wooden cleats with C.P screws, washers, including cost of materials, labour complete as per specifications.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	1418.63	Rupees One Thousand Four Hundred Eighteen And Paise Sixty Three Only
62	2	✓	Providing and fixing C.P. brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P. brass screws including cost of materials, labour complete as per specifications.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	887.92	Rupees Eight Hundred Eighty Seven And Paise Ninety Two Only
63	2	✓	Providing and fixing sand cast iron soil waste single equal junction of required degree with access door 1 00x1 00x1 00mm, insertion of rubber washers 3mm thick bolts and nuts, including cost of materials, labour, testing complete as per specifications. KBS 11-1.10.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	1145.34	Rupees One Thousand One Hundred Forty Five And Paise Thirty Four Only
64	6	✓	Providing and fixing sand cast iron soil waste 152mm offsets for 100 mm pipes, including cost of materials, labour, testing complete as per specifications. Specification No. KBS 11.1.1 0as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	819.88	Rupees Eight Hundred Nineteen And Paise Eighty Eight Only
65	4	✓	Providing stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary.(Rate includes cost of all materials, fixtures and lead). 10 cms x 10cms as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	209.79	Rupees Two Hundred Nine And Paise Seventy Nine Only
66	6	✓	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 Kg/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquisitions and testing complete as per specifications. 140 mm dia as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	755.24	Rupees Seven Hundred Fifty Five And Paise Twenty Four Only
67	20	✓	Providing and fixing sand cast iron soil waste and vent pipes 100mm dia with spun yarn soaked in cement slurry and cement mortar 1:2 including cost of materials, labour, testing complete as per specifications. KBS 11-1.10 as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	798.34	Rupees Seven Hundred Ninety Eight And Paise Thirty Four Only
68	100	✓	Providing and laying in position to required level or slope 150 mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications. Specification No. KBS 12.2.5 I 12.7 as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	400.30	Rupees Four Hundred And Paise Thirty Only
69	4	✓	Constructing brick masonry inspection chamber 455x610mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 600 x 600 x 450 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1 :3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	10153.84	Rupees Ten Thousand One Hundred Fifty Three And Paise Eighty Four Only

Contractor

Sl No		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
				Unit	Rate in Words	Rate in Figures
1		2	3	4	5	6
70	✓	3	Constructing brick masonry circular type manhole 1.22 m internal dia at bottom 1.68 m deep and 0.56m dia at top, with table moulded and non modular bricks of class designati on 50 in cement mortar 1 :4, inside cement plaster 12mm thick with cement mortar 1 :3, finished with a floating coat of neat cement, foundation concrete M 1 0 using 40mm and down size granite metal and making necessary channel in cement concrete M 15 with 20mm and down size granite metal, finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter conforming to IS :12592, total weight length of cover and frame to be not less than 182 kg, fixed in cement concrete M 15 20mm and down size broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Specification No. KBS 12.4 11.40 as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	29624.62	Rupees Twenty Nine Thousand Six Hundred Twenty Four And Paise Sixty Two Only
71	✓	18	Providing 20mm square M.S footrest and fixing in manhole with M 1 0 cement concrete block of 20x20x1 0cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6 as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	278.96	Rupees Two Hundred Seventy Eight And Paise Ninety Six Only
72	✓	1	Making connection of drain or sewer line of size 100 to 230mm external dia with existing manhole including breaking into and making good the walls, floors with cement concrete M 15 with 20mm and downsize granite metal, cement plastered on both sides of mix 1 :3, finished with a floating coat of neat cement, and making necessary channels for the drain, including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Nos	1966.36	Rupees One Thousand Nine Hundred Sixty Six And Paise Thirty Six Only
73	✓	29.28	Providing 20mm thick cement plaster in single coat with cement mortar 1 :3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, including providing and removing scaffolding, cost of materials, labour, curing etc., complete as per specification.KSRB 15-4.7 Extra for providing and mixing waterproofing compound in cement plaster for brick masonry work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1 :4, 20mm thick cost of materials complete as per specifications.as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sqm	305.05	Rupees Three Hundred Five And Paise Five Only
74	✓	77.8	Electrical Items :- Supplying.....mm dia 2mm2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary(2/2) b) 25mm dia 2mm thick as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	59.85	Rupees Fifty Nine And Paise Eighty Five Only
75	✓	88	Groove cutting in the wall supplying dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.(2/3) b) 25mm dia 2mm thick (P-2, I-3b) as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	tonne	60.90	Rupees Sixty And Paise Ninety Only
76	✓	8	Supply and fixing of metal fan hook box as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	145.95	Rupees One Hundred Forty Five And Paise Ninety Five Only

Contractor

SI		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
No	Unit			Rate in Words	Rate in Figures	
1	2		3	4	5	6
77	8		Supplying and flush mounting teak wooden box without front plank made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete. (3/6) d) 8"x6"x3" as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	71.40	Rupees Seventy One And Paise Forty Only
78	32		Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. (3/8) l) Point wiring using Group A Materials a) Short point up to 3M from tapping point to out let via switch as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	257.25	Rupees Two Hundred Fifty Seven And Paise Twenty Five Only
79	32		Supply and fixing of bakelite D.P/Socket/ switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches.(6/14)l) Using Group 'A' Material. l) Using Group 'A' Material. a) 32Amps Flush/project type DP switch as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	196.35	Rupees One Hundred Ninety Six And Paise Thirty Five Only
80	663.2		Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring .(9/20) l) Group A Materials. l) Group A Materials. b) 1.5 sqmm as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	15.75	Rupees Fifteen And Paise Seventy Five Only
81	2400		Supplying 4mm thick plastic sheet with necessary niches for fixing switches regulators etc., and fixing on existing wooden or metal box using N.F. screws as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Sq.Cm	0.26	Rupees And Paise Twenty Six Only
82	8		Supply and fixing of 230 volts CFL lamp holder as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	87.15	Rupees Eighty Seven And Paise Fifteen Only
83	8		Supplying and fixing cast Aluminium round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp as required. a) Group 'A' as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	2648.10	Rupees Two Thousand Six Hundred Forty Eight And Paise Ten Only
84	6		Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, and 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved. (23/23) l) 56" Sweep (1400mm) a) Regular model (Khaitan, Crompton Greaves, Orient, Polar, Bajaj, Havells/Usha) l) 56" Sweep (1400mm). .Item No 9.3.3, as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	2625.00	Rupees Two Thousand Six Hundred Twenty Five Only
85	8		Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete.(30/3) c) 63 Amps as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	245.70	Rupees Two Hundred Forty Five And Paise Seventy Only
86	8		Digging of trench of 0.6m deep x 0.50 M wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) (68/12) a) In hard soil as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	81.90	Rupees Eighty One And Paise Ninety Only
87	89.6		Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc.,as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	M	20.48	Rupees Twenty And Paise Forty Eight Only

A.K.B.

Contractor

Page 12 of 13

SI		App Qty	Description of work	Approved Rates of BALAKRISHNA ARUN KUMAR		
No				Unit	Rate in Words	Rate in Figures
1	2	3		4	5	6
88	2		Supplying, fixing, Wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 M long buried in a pit . . The pit should be filled with equal proportion of salt and charcoal 150mm allround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and checkouts etc, the pipe shall have 16 through holes of 122 mm dia Supplying as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	2863.35	Rupees Two Thousand Eight Hundred Sixty Three And Paise Thirty Five Only
89	6		Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate.is 3854 and IS 1293. Item No 9.2.1, as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	300.30	Rupees Three Hundred And Paise Thirty Only
90	2		Supplying exhaust fan of 1440 RPM of 300mm (12") size with bracket blades complete for light duty suitable for operate on 230V 50Hz, AC Supply.Item No 9.2.1, as per direction of Engineer-in-charge ---- All terms and conditions are as per Tender Document	Each	3836.76	Rupees Three Thousand Eight Hundred Thirty Six And Paise Seventy Six Only



 18/12/17



 Contractor